

INSTALLATION GUIDE — AquaPearl 500 Pro

Document type: guide | Product line: AquaPearl 500 Pro | Last updated: 2026-01-01

1. PRE-INSTALLATION CHECKLIST

- Water pressure between 20-80 psi at the installation point
- Standard under-sink cold water supply line with shut-off valve
- Grounded electrical socket within 1.5m of the installation point
- At least 35cm of vertical clearance under the sink

2. TOOLS REQUIRED

Adjustable wrench, Phillips screwdriver, tubing cutter (included in some kits)

3. UNDER-SINK INSTALLATION STEPS

Step 1: Turn off the cold water supply valve under the sink.

Step 2: Attach the T-valve adapter to the existing cold water supply line.

Step 3: Connect the inlet tubing from the T-valve to the unit's inlet port.

Step 4: Mount the unit to the cabinet wall using the bracket and screws provided.

Step 5: Connect the outlet tubing from the unit to the dedicated faucet.

Step 6: Drill a hole in the sink or countertop for the dedicated faucet if one is not already present.

Step 7: Turn the water supply back on and check all connections for leaks.

4. FIRST-RUN FLUSHING PROCEDURE

This step is required and is the most commonly skipped step. After installation, run the dedicated faucet continuously for 10 minutes before first use. This flushes air and manufacturing residue from the filter cartridges and tubing. Skipping this step is the most common cause of odd-tasting water or unusual pump noise immediately after installation.

5. PROFESSIONAL INSTALLATION

Professional installation can be booked through the website for a fee of \$49.99, which includes the full installation and first-run flushing performed by a certified technician.

6. WHAT VOIDS THE WARRANTY DURING SELF-INSTALLATION

Using non-standard fittings, forcing connections that do not fit, or installing outside the specified water pressure and temperature range will void the warranty per the Warranty Policy. If you are unsure about your plumbing setup, book professional installation instead.